

**NOTICE:**  
For your safety, you are required by Texas Law to call 811 at least 48 hours before you dig so that underground lines can be marked. This signature does not fulfill your obligation to call 811.

**VERIFICATION OF PRIVATE UTILITY LINES**  
*Mike Brower* Date: 11/29/23  
CenterPoint Energy natural gas utilities shown. (Gas service lines are shown). This signature not to be used for conflict verification.  
Signature Valid for six months.

*Mike Brower* Date: 11/29/23  
CenterPoint Energy/UNDERGROUND Electrical Facilities Verification ONLY.  
(This signature verifies existing underground facilities - not to be used for conflict verification.)  
Signature Valid for six months.

**CAUTION!!**  
EXISTING UNDERGROUND UTILITIES IN THE AREA. CONTRACTOR IS RESPONSIBLE FOR DETERMINING THE HORIZONTAL AND VERTICAL LOCATION OF ALL UTILITIES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY REPAIRS TO EXISTING UTILITIES DUE TO DAMAGE INCURRED DURING CONSTRUCTION. CONTRACTOR SHALL NOTIFY THE ENGINEER OF ANY DISCREPANCIES ON THE PLANS.

(2) Type 3 barricades posted on both sides of roadway pipe crossing location, with detour ahead signs on Hwy 105 for the neighborhood notification. Road closed ahead signs posted on Navajo headed towards road closure, and on Hwy 105 side of Navajo Dr.

**KEYED NOTE**  
# PROP. CULVERT CROSSING

- NOTES:**
1. PROVIDE EDGE BACKFILL ALONG THE NEWLY OVERLAYED STREETS, AS NECESSARY, ON OPEN-DITCH SECTIONS. NO SEPARATE PAY.
  2. EXTEND ASPHALT STABILIZED BASE A MINIMUM OF 2' BEYOND EDGE OF ASPHALT PAVEMENT.
  3. HYDROSEED ALL DISTURBED AREAS.
  4. FIELD VERIFY ALL EXISTING CONDITIONS AND ELEVATIONS PRIOR TO CONSTRUCTION. NOTIFY THE ENGINEER OF ALL DISCREPANCIES PRIOR TO BEGINNING ANY WORK.
  5. CONTRACTOR TO MAINTAIN ACCESS TO PROPERTIES DURING CONSTRUCTION.
  6. FULL ROADWAY CLOSURE NOT ALLOWED. IMPLEMENT "ONE-LANE, TWO-WAY TRAFFIC CONTROL" PER TCP (1-2) -18.


THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY ANN M. COLINA, P.E. 93420

ON August 8, 2023

**CITY OF CONROE**  
ENGINEERING  
700 METCALF ST. P.O. BOX 3066  
CONROE, TEXAS 77305 (936) 522-3100

DRAWING NAME: OVERALL LAYOUTS.DWG  
PATH: H:\Projects\Projects\Street Paving\2022-01\_Street Rehab - Lake Conroe Forest Phase I\Drawings  
GRAPHIC SCALE:

SCALE: NTS



STREET REHAB - LAKE CONROE FOREST PHASE I

OVERALL - PROPOSED OVERLAY KEYSHEET  
**EXHIBIT - CULVERT WORK**

DRAWN BY: E1	Design By: EHR5
REVIEWED BY: AMC	
FLAT FILE NO:	
Project No: 2022-01	
SCALE: NTS	DATE: August 8, 2023
	Sheet No: 7

"NOT FOR CONSTRUCTION" REVIEW ONLY